



HOWE STREET

	From	To	Colour	
1	-3.5	-4.5	red 032	Cut (m)
2	-2.5	-3.5	red 048	
3	-1.5	-2.5	red 088	
4	-1.5	-1	red 120	
5	-1	-0.5	red 176	
6	-0.5	-0.15	red 232	
7	-0.15	0.15	off yellow	
8	0.15	0.5	green 232	Fill (m)
9	0.5	1	green 136	
10	1	1.5	green 096	
11	1.5	2	green 056	
12	2	2.5	yellow 239	
13	2.5	3	orange	
14	3	4	brown	
15	4	5	rgb(114,59,9)	
16	5	6	rgb(76,40,6)	

Total Fill Volume = 1668.16m³
 Total Cut Volume = 2586.47m³

Warning:
 All contours, ground levels and features shown on this plan have been shown only for purposes intended in the instructions from this Client. This information is not to be used for any other purpose, without prior consultation and consent from Churchill LDS Ltd. No liability is accepted for misuse of this information.

COPYRIGHT: The copyright of this document is retained by Churchill LDS Ltd. This Client shall own the factual information contained hereon only after payment by this Client.

Churchill LDS
 surveyors • engineers • planners

P.O. Box 64 246
 Botany
 Auckland 2163
 Tel: (09) 273 4182
 Fax: (09) 273 4309
 Email: admin@clds.co.nz

EARTHWORKS PLAN
 ISOPACH

PROJECT: 27,35 & 35A HOWE STREET, HOWICK

AMENDMENT SCHEDULE		CLIENT: LUMINA DEVELOPMENTS LTD	
		AUTOCAD: N/14015/autocad/rc/isopach	SCALE: 1:600 (A3)
		CIVILCAD: 14015.12d	DATE DRAWN: MAY 2017
		SURVEYOR: BH DRAWN: MCM	14015-69-01
		DESIGNED: KBA CHECKED: KBA	